E04-03

- TYPICAL CROSS - SECTION THRU CLASSROOM -

SCALE: 3/4" = 1'-0

- TYPICAL FLASHING DETAIL -

SCALE: HALF FULL SIZE

- SECT AT UNIT VENT -

SCALE 3" = 1'-0"

- SCHEDULE OF INTERIOR MATERIALS & FINISHES -

SPACE	FLOOR M	FLOOR F	WALLS M	WALLS F	CEILING M	CEILING F	WAINSCOT M	WAINSCOT F	BASE M	BASE F	DOOR WINDOW CIL M	DOOR WINDOW CIL F	TOOL EQUALS M	TOOL EQUALS F	SASH M	SASH F	DOORS M	DOORS F	FRAMES (CASES) DOORS M	FRAMES (CASES) DOORS F	REMARKS	KEY TO SYMBOLS	MATERIALS
CORRIDOR #1	AT W	EWP	ACT PF	—	GYP EWP	ALUM	—	—	WP EWP	—	—	—	—	—	—	—	—	—	EXP CON - EWP			AT	ASPHALT TILE
CORRIDOR #2	AT W	EWP	ACT PF	—	GYP EWP	ALUM	—	—	WP EWP	—	—	—	—	—	—	—	—	—	EXP CON - CWP			LT	LIGHTWEIGHT CONCRETE
CORRIDOR #3	AT W	FB	ACT PF	—	GYP EWP	ALUM	—	—	WP EWP	—	—	—	—	—	—	—	—	—	EXP CON - CWP			BC	BRICK
CORRIDOR #4	AT W	FB	ACT PF	—	GYP EWP	ALUM	—	—	WP EWP	—	—	—	—	—	—	—	—	—	EXP CON - CWP			BC	BRICK PLYWOOD
LOBBY	AT W	EWP	ACT PF	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	EXP CON - CWP			CB	CONCRETE BLOCK
CLASSROOMS	AT W	EWP	ACT PF	FB	GYP EWP	ALUM	WD	BR	WP EWP	—	MAT	BR	AL	—	BK	AL	BK	AL	EXP CON - CWP			CT	CERAMIC TILE
BOYS	TERR —	EWP	ACT PF	QT	GYP EWP	ALUM	—	—	WP EWP	—	—	—	—	—	—	—	—	—	EXP CON - CWP			PL	PLASTIC
GIRLS	TERR —	EWP	ACT PF	QT	GYP EWP	ALUM	—	—	WP EWP	—	—	—	—	—	—	—	—	—	EXP CON - CWP			FB	FACE BRICK
BOILER ROOM	CON —		CON		—	ST	ALUM	AL	—	—	—	—	—	—	—	—	—	—	—			ST	SAND - LIME
BOOK STORE	LT W	—	ACT PC	FB	—	ST	ALUM	AL	—	—	—	—	—	—	—	—	—	—	EXP CON - PWP			AL	ALUMINUM
VAULT	LT W	PL	CON	CWP	—	RT	PF	—	—	—	—	—	—	—	—	—	—	—				MAT	MASTIC
GENERAL OFFICE	AT W	EWP	ACT PF	FB	—	ST	ALUM	AL	—	—	—	—	—	—	—	—	—	—	EXP CON - PWP	RT LT CAB		RT	RUBBER TILE
WAITING	AT W	EWP	ACT PF	FB	—	ST	ALUM	AL	—	—	—	—	—	—	—	—	—	—	EXP CON - PWP	RT LT CAB		RT	CORKTEX TILE
PRINCIPAL	AT W	EWP	ACT PF	FB	—	ST	ALUM	AL	—	—	—	—	—	—	—	—	—	—	EXP CON (NWP) PWP			TERR	TERRAZZO
TOILET #1	AT W	EWP	ACT PF	QT	—	ST	ALUM	—	—	—	—	—	—	—	—	—	—	—	EXP CON - CWP			AL	ALUMINUM
CONFERENCE	AT W	EWP	ACT PF	FB	—	ST	ALUM	AL	—	—	—	—	—	—	—	—	—	—	EXP CON - CWP			ST	STEEL
STORAGE	AT W	FB	ACT PF	—	—	ST	ALUM	AL	—	—	—	—	—	—	—	—	—	—	EXP CON - CWP			AL	ALUMINUM
PRINTING	AT W	EWP	ACT PF	FB	—	ST	ALUM	AL	—	—	—	—	—	—	—	—	—	—	EXP CON - EWP (CWP)			AL	WOOD
																						F	FINISHED
																						ENAM	ENAMEL
																						PWP	PLAY WALL PAINT
																						PF	PCE FINISHED
																						EXW	EXPOSED WOOD
																						W	WAX

NOTE:
THE ROOM FINISH SCHEDULE IS SUPPLEMENTARY ONLY & IS NOT INCLUSIVE. THIS SCHEDULE DOES NOT EXCLUDE WORK SHOWN ON DETAILED DRAWINGS OR CALLED FOR IN THE SPECIFICATIONS.

- EXPANSION JOINT CO -