

1. SEE SHEET #4-16 FOR GENERAL NOTES, LEGEND, AND SCHEDULES.
2. REMOVE SECTION OF EXISTING 22" X 12" DUCT AS SHOWN. CONNECT NEW 22" X 12" DUCT TO EXISTING 22" X 12" DUCT AS SHOWN.
3. REMOVE EXISTING EXHAUST FAN AND REPLACE WITH NEW ONE. VERIFY LOCATION.
4. REMOVE EXISTING 18" X 12" RETURN AIR GRILLE. STOP RETURN AIR DUCT FROM EXISTING WALL OPENING DOWN THROUGH BULKHEAD TO NEW 18" X 12" RETURN AIR GRILLE.
5. DISCONNECT EXISTING SINKS AND SINKS EQUIPMENT IN THIS AREA. REMOVE EXISTING SINKS AND WASTE, SINKS, AND DRAINAGE EQUIPMENT TO A POINT BELOW FINISHED FLOOR. WALL AND CEILING SURFACES, THEN PLUG AND CAP.
6. REMOVE EXISTING 48" X 8" SUPPLY AIR REGISTER. CONNECT NEW 34" X 8" DUCT TO EXISTING 36" X 8" DUCT.
7. EXISTING DUCT WORK AND GRILLES SHALL REMAIN. VERIFY LOCATION.
8. STUB 10" X 6" DUCT WITH DAWNER INTO CHASE. (120 CFM)
9. REMOVE EXISTING THERMOSTAT. REPLACE WITH NEW THERMOSTAT IN NEW LOCATION AS SHOWN.
10. REMOVE EXISTING CLASSROOM UNIT VENTILATOR AND REPLACE AS SHOWN. CONNECT EXISTING 1" SUPPLY AND RETURN PIPING TO NEW UNIT VENTILATOR.
11. REMOVE EXISTING OUTDOOR AIR INTAKE DUCT AND GOOSENECK ON ROOF. REPLACE WITH NEW 24" O.D. OUTDOOR AIR INTAKE AND DUCTWORK AS SHOWN.
12. REMOVE AND REPLACE EXISTING THERMOSTAT.