

ROOM NO.	ROOM NAME	AREA S.F.	CEILING HEIGHT
Q201	MEZZANINE	2181	--
Q202	MECHANICAL ROOM	159	--

1 INDICATES BULKHEAD LINE ABOVE--- REFER TO INDICATED SECTIONS, DETAILS, REFLECTED CEILING PLANS, AND INTERIOR ELEVATIONS.

2 LOCKER BASE - SEE SECTION 5-A7.29

- ## FLOOR PLAN NOTES

1. WHERE DIFFERENT FLOOR MATERIALS MEET THEY SHALL MEET UNDER THE CENTERLINE OF THE FLOOR, UNLESS NOTED OTHERWISE.
2. WALLS THAT DO NOT LAY OUT IN FULL OR HALF UNITS SHALL BE NOTED AS SUCH.
3. INTERIOR WALLS SHALL BE BUILT OUT UP TO THE CENTERLINE OF THE ROOM. WALLS TO BE BUILT AT THE REAR FLEED WITH PRESISTING AT RATED WALLS PER SPEC. SEC. 0120 AND BUILT IN ALLOCATION AT NON-RATED WALLS THAT ARE BUILT FOR DEFLECTION.
4. SEE DETAILS ON SHEET A1.3 FOR TYPICAL MASONRY CONTROL JOINTS AND EXPANSION JOINTS.
5. SNAIL WALK THE MASONRY WALLS ARE INDICATED AT NOMINAL DIMENSIONS.
6. EXPOSED CONCRETE MASONRY JUNE (CNU) CORNERS SHALL BE FINISHED WITH A 1/2" THICK CONCRETE FINISH CORNER, INCLUDING THOSE THAT ARE ADJACENT TO LOCKERS. USE BALUNES CORNER UP TO UNDERBONE OR CEILING TO BULLHEAD FLAME. ABOVE THIS PLANE USE CNU 1/2" BULLHEAD CORNER.
7. FINISH FLOOR ELEVATION INDICATED FOR THE BUILDING IS 10'-0". REFER TO THE SITE PLAN FOR CONCRECTION TO USE AS DATUM.
8. SEE SHEET A1.26 FOR MOUNTING HEIGHTS.
9. INTERIOR AND EXTERIOR WALLS ARE TO BE RUNNING BOND UNLESS NOTED OTHERWISE. EXTEND A MINIMUM OF 4" ABOVE THE HIGHEST CEILING.
10. ALL DIMENSIONS INDICATED ARE NOMINAL. METAL STUD WALLS ARE DIMENSIONED TO FACE OF STUD. REFER TO THE SPECIFICATIONS FOR DIMENSIONS FOR ACTUAL DIMENSIONS, WHERE INDICATED.
11. UNLESS OTHERWISE NOTED, THE WALL LENGTH FROM THE OUTER EDGE OF DOOR/JITE ROOM OPENING (HENCE SIDE OF THE FRAME) TO THE NEAREST INTERSECTING WALL SHALL BE 10'-0".
12. REFER TO SHEET A1.3 FOR WALL TYPES.
13. GENERAL NOTE: BUILDING DIMENSIONS ARE TO FACE UNLESS OTHERWISE NOTED.
14. FINISH FLOOR ELEVATION = 10'-0" FOR THE FIRST FLOOR AND 11'-0" FOR THE SECOND FLOOR, UNLESS OTHERWISE NOTED.