

NOTE:
FOR ADDITIONAL MASONRY BOND BEAM
AND MASONRY UNITEL INFORMATION
SEE S3.1 to S3.9 & S5.1 to S5.9

KEYNOTES

1. FINISH GRADE - REFER TO SITE DRAWINGS.
2. CONCRETE FOOTING - REFER TO STRUCTURAL DRAWINGS.
3. FOUNDATION WALL - REFER TO STRUCTURAL DRAWINGS.
4. 2" FLEXIBLE INSULATION - REFER TO STRUCTURAL DRAWINGS.
5. 4" SPACER FILL OVER WARP BARRIER OVER 4" DRAINAGE FILL.
6. CONCRETE SLAB - REFER TO STRUCTURAL DRAWINGS.
7. 3" DIA. X 8' ANCHOR BOLT WITH HOOK AT 32" O.C. BY SECTION 04150.
8. 1/2" WALL FLASHING WITH WEIR HOLES REFER TO SECTION 04150 AND 04200.
9. 1/2" EXPANSION JOINT MATERIAL - REFER TO SECTION 04200.
10. 2" FLEXIBLE INSULATION - REFER TO SECTION 04200.
11. 4" CONCRETE MASONRY UNIT - REFER TO SECTION 04200.
12. 8" CONCRETE MASONRY UNIT - REFER TO SECTION 04200.
13. 12" CONCRETE MASONRY UNIT - REFER TO SECTION 04200.
14. 8" CONCRETE MASONRY UNIT - REFER TO SECTION 04200.
15. 12" CONCRETE MASONRY UNIT - REFER TO SECTION 04200.
16. 12" CONCRETE MASONRY UNIT - REFER TO SECTION 04200.
17. 12" CONCRETE MASONRY UNIT - REFER TO SECTION 04200.
18. FACE BRICK COLOR "A" - REFER TO SECTION 04200.
19. FACE BRICK COLOR "B" - REFER TO SECTION 04200.
20. CAST STONE - REFER TO SECTION 04200.
21. CAST STONE CORNER - REFER TO SECTION 04200.
22. FILL CAU CORE WITH GROUT.
23. CAU BALANCE - REFER TO SECTION 04200.
24. CAU BOND BEAM - REFER TO STRUCTURAL DRAWINGS.
25. STEEL COLUMN - REFER TO STRUCTURAL DRAWINGS.
26. STEEL BEAM - REFER TO STRUCTURAL DRAWINGS.
27. STEEL ANGLE - REFER TO STRUCTURAL DRAWINGS.
28. STEEL PLATE - REFER TO STRUCTURAL DRAWINGS.
29. STEEL JOINT - REFER TO STRUCTURAL DRAWINGS.
30. STEEL JOINT - REFER TO STRUCTURAL DRAWINGS.
31. STEEL JOINT - REFER TO STRUCTURAL DRAWINGS.
32. STEEL JOINT - REFER TO STRUCTURAL DRAWINGS.
33. 1/2" METAL DECK - REFER TO STRUCTURAL DRAWINGS.
34. CONCRETE SLAB OVER METAL DECK - REFER TO STRUCTURAL DRAWINGS.
35. STAIR LANDING - REFER TO DETAIL 1-A101.
36. 1/4" O.D. STEEL PIPE GUARD RAIL AT TOP AND VERTICAL SUPPORTS PROVIDE VERTICALS AT 5'-0" O.C. (MAX.) AND SET IN SLEEVES.
37. TREATED WOOD BLOCKING, SIZE AS INDICATED.
38. 4" BATT INSULATION - REFER TO SECTION 07110.
39. 2" BATT INSULATION - REFER TO SECTION 07110.
40. 1" BATT INSULATION - REFER TO SECTION 07110.
41. 1/2" BATT INSULATION - REFER TO SECTION 07110.
42. 1/4" BATT INSULATION - REFER TO SECTION 07110.
43. PREPARED METAL ROOFING - REFER TO SECTION 07120.
44. ADHERED FLEXIBLE SHEET ROOFING - REFER TO SECTION 07120.
45. METAL FLASHING - REFER TO SECTION 07120.
46. METAL FLASHING AND GRAVEL STOP - REFER TO SECTION 07120.
47. SEALANT WITH BACKER ROD - REFER TO SECTION 07120.
48. PACK WITH BATT INSULATION.
49. 2 LAYERS OF 1/2" PARALLEL ROOF INSULATION THICKED ROOF INSULATION - 1/4" PER FOOT SLOPE MIN. (7" MAX. THICKNESS AT ROOF DRAIN).
50. 1" RECOVERY BOARD.
51. SHIMMER MOUNTED REELIT & COUNTERFLASHING.
52. EXPANSION JOINT MATERIAL WITH SPOUSE TUBING 3" METAL DECK - REFER TO STRUCTURAL DRAWINGS.
53. PROVIDE FLEXIBLE SHEET ROOFING MANUFACTURER'S STANDARD FLASHING DETAIL OVER PARAPET WALL.
54. FLASHING - REFER TO SECTION 08800.
55. HOLDING METAL DOOR & FRAME - REFER TO ALUMINUM FRAME - REFER TO SECTION 08120 AND PER DOOR - REFER TO SECTION 08120.
56. ALUMINUM WINDOW - REFER TO SECTION 08120.
57. FINISH BASE - REFER TO FINISH SCHEDULE.
58. FINISH CEILING - REFER TO FINISH SCHEDULE.
59. GYPSUM PLASTER OVER METAL LATH - REFER TO SECTION 09200.
60. VERTICAL WINDOW SILL - REFER TO SECTION 09200.
61. ROOFING AND DRAINAGE CHANNELS - REFER TO SECTION 09200.
62. 3/4" METAL STUD FRAMING AT 16" O.C.
63. 8" METAL STUD FRAMING AT 16" O.C.
64. 1/2" RIB-REINFORCED OPSUM WALLBOARD.
65. 1/2" TIE 1/4" OPSUM WALLBOARD.
66. SHOWN WOOD - REFER TO DETAIL 5-A8.1 AND SECTION 0910.
67. OPERABLE WALL - REFER TO SECTION 10550.
68. THICKER PLATES ARE TO BE DESIGNED.
69. LIGHT FIXTURE - REFER TO ELECTRICAL DRAWINGS.
70. STEEL RISERS - REFER TO STRUCTURAL DRAWINGS.
71. ALTERNATE SLOPED CEILING PROJECTION SURFACE AND SECTION 0910.
72. REVEAL DRYWALL TRIM - REFER TO DETAIL 4-A81 AND SECTION 09250.
73. 1/4" OPSUM SHEATHING.

3 WALL SECTION
1/2"=1'-0"

2 WALL SECTION
1/2"=1'-0"

1 WALL SECTION
1/2"=1'-0"

WALL SECTIONS

DRAWN BY: DMR
CHECKED BY: LEC

COMM. NO.: 95067.00
DATE: APRIL 21, 1997

REVISIONS NO. DATE

A5.7

Fanning/Howey
Associates, Inc.

Architects Engineers Consultants

THE NEW
CHESTERTON HIGH SCHOOL
FOR THE
DUNELAND SCHOOL CORPORATION
CHESTERTON, INDIANA

COPYRIGHT 1997 BY FANNING/HOWEY ASSOCIATES, INC.

10/10/97

10/10/97