

PLAN TYPE	MANUFACTURER/CATALOG	MOUNTING	NO.	LAMP WATTS	TYPE/LU	APPLIED VOLTAGE	DESCRIPTION
FR-2	LITTONIA 59832 METALLIC W32M1125 L1000LITE W32M235-A1B125 COLUMBIA AWM23A-A12.125	SURF / SUSP.	2	90	F032/78 41K	2900	4 FOOT WMAP AROUND TWO LAMP FLUORESCENT OR SUSPENDED. SEE DRAWINGS
FR-4	LITTONIA 59432 METALLIC W32M1125 DAY-BRITE T3M432-A12.125 COLUMBIA AWM23A-A12.125	SURF / SUSP.	4	180	F032/78 41K	2900	4 FOOT WMAP AROUND FOUR LAMP FLUORESCENT OR SUSPENDED. SEE DRAWINGS.
FS-32A	COLUMBIA FSS-232-ASV LITTONIA 55532 LITTONIA 55532 DAY-BRITE T3S22 ASY-6	SURF.	2	90	F032/78 41K	277	4 FOOT LONG FLUORESCENT STAGGERED STRIP WITH ASYMMETRIC REFLECTOR. MOUNT FIXTURE IN LIGHT COVE PER DRAWINGS.
FSR-22	DAYBRITE 23ACGF40-F901	SUSPENDED	3	135	F40/30X/ SYXAI 2850	277	2 x 3. THREE LAMP SURFACE FLUORESCENT PER DRAWINGS. FLUXTURE HOUSING TO BE PAINTED FLAT BLACK.
FS3-2	L.C. DOANE ST3278-2-48R120-76WK	SURFACE	2	90	F032/41K 2800	120	2 LAMP STAINLESS STEEL FLUORESCENT FIXTURE MOUNTED IN GREENHOUSE. PROVIDE CHAINS FOR LOWERING PER DRAWINGS.
FS3-4	MORLITE S01244-SS-55	PENDANT	4	180	F032/41K 2900	277	2 x 4' PENDANT MOUNTED STAINLESS STEEL FLOOR. FIXTURE, GASKETED ENCLOSURE.
FLY-2	KENALL 7270 FALL-SAFE FTS-2-232 L.C. DOANE SW9322D00-1500APKX	SURF / SUSPEND	2	90	F032/41K 2900	277	4' LONG WMAP AROUND FLUORESCENT FIXTURE FOR HIGH SURE AREA. PROVIDE 16 GA ST. BACK-PLATE FOR SUSPENDED MOUNTING LOCATIONS.
FM-3	MORLITE R47R-142-BSAL MORRIS KIRZTON VEC232 DAY-BRITE 20M332-1501 L.C. DOANE CR-3581CF-3530APKX	RECESSED	3	135	F032/41K 2900	277	2 x 3. LAY-IN FLOOR. FIXTURE WITH DOUBLE GASKETED DOOR. U.L. LISTED FOR WET LOCATION. 18 GA. STEEL. 187" POLY-ETHYLENE GLASS LENS ON THE ENVIRONMENTAL THE FIXTURE SIDE
FM-4	MORLITE R47R-142-BSAL MORRIS KIRZTON VEC232 FALLSAFE OF L24432-80-95-E882 L.C. DOANE CR-4040CF-3530APKX PRUDENTIAL P-2124-48CT50	RECESSED	4	180	F032/41K 2800	277	2 x 4'. LAY-IN FLOOR. FIXTURE WITH DOUBLE GASKETED DOOR. U.L. LISTED FOR WET LOCATION. 18 GA. STEEL. 187" POLY-ETHYLENE GLASS LENS ON THE ENVIRONMENTAL THE FIXTURE SIDE
FM-1	MORLITE H787R-9870C HALO H787R-9870C LITTONIA AF-2760T1 6AR-JPF STAFF 710-BL-JPF	RECESSED	2	97	QUAD 121 (12)X60-25 DULX-0-25 1800	277	10" WET LOCATION OW. RISE (41K) QUAD COMPACT LAMP. SENSITIVE BALLAST
FMF-1	MORLITE R47R-142-BSAL MORRIS KIRZTON VEC232 DAY-BRITE 20M332-1501 L.C. DOANE CR-3581CF-3530APKX	RECESSED PLANNED	2	90	F032/41K 2900	277	1 x 4'. LAY-IN FLOOR. FIXTURE WITH DOUBLE GASKETED DOOR. U.L. LISTED FOR WET LOCATION. 18 GA. STEEL. 187" POLY-ETHYLENE GLASS LENS ON THE ENVIRONMENTAL THE FIXTURE SIDE
K-2	INDY 200R 61-BMG OR LITTONIA 59832 PRESCOTT 1224-3582 KIRBY VERNER J7131	RECESSED	1	200	200/A19	130	8' APERTURE. 200 WATT INCANDESCENT DOWN LIGHT WITH A CLEAR REFLECTOR AND BLACK BOTTLE.
K-3	APPLETON VPM010G RIG-A-LITE VPM0206075 G.E. HBX30F3MK	WALL	1	200	200 P330 991F	130	ELEVATOR PIT INCANDESCENT FIXTURE WITH PORCELAIN REFLECTOR AND WIRE GUARD.
K-4	COLE 5252-NURSE	WALL	1	25	25W/A19	130	WALL MOUNTED SMALL RECESSED NURSE CALL LIGHT.
K-6	APPLETON VPM010G RIG-A-LITE VPM0206075 G.E. HBX30F3MK	WALL	1	200	200 P330 991F	130	WALL MOUNTED INCANDESCENT FIXTURE WITH PORCELAIN REFLECTOR AND WIRE GUARD.
K-7	RAMBUSH PD-150 SERIES	PENDANT	1	150	150Q QUARTZ	120	150 WATT PENDANT MOUNTED QUARTZ FIXTURE. TO BE BLACK. STEM LENGTH PER DRAWINGS.
NO-1	ALICO R-2058-1	RECESS	1	15	15W/A19	120	DARK ROOM SAFELIGHT RECESS MOUNTED. RECESSED.
NO-2	COLE 5252-IN USE	RECESS WALL	1	25	25W/A19	120	INCANDESCENT RECESS WALL MOUNTED IN USE LIGHT FOR DARKROOMS. PROVIDE THE WORDING "IN USE" ON SIGN.
RM-1	KIRCHER K-624 LITGOLLER 40909 SERIES SEACOLL 4739 QUORUM 5016-4-2-PB	WALL	3	40	40925/W	120	ABOVE MIRROR WALL MOUNTED DEGRATIVE FIXTURE WITH POLISHED BRASS OPEN WIRE GUARDS FOR EACH LAMP.
LB-1	LITTONIA TALE20M420	SUSPENDED	1	265	M3250/ U	277	LOW BAY INDUSTRIAL HLD WITH SAFETY CHAIN. IN MOUNTING THE LIGHT AS PER DRAWINGS. ALUMINUM HOUSING AND INSULATION INCLUDED. PROVIDE QUARTZ RESISTIVE ON FIXTURES WITH "Q" SUFFIX.
M-1	HOLOPRANE FRS-40MMHTT-F31- F1P3CB-UPH-35-08214-2-WC M-10	SUSP.	1	465	MIRAO/ WBA/JF 40000	277	H-LAY INDUSTRIAL HLD WITH SAFETY CHAIN AND WIRE GUARD. HLD. HEIGHT AS PER DRAWINGS. FOR M-10 PROVIDE WITH QUARTZ THROUGH POWER ROCK. E31 REFLECTION
M-2	LITTONIA L11155 HALO M700-405-773P PRESCOTT 930575100HPSF8M KIRBY VERNER V6958-DL-F	RECESSED	1	130	LU100 9500	277	RECESSED LOW BAY PRESSURE SODIUM DOWNLIGHT WITH TEMPERED GLASS LENS AND TEMPERED FRESHEN GLASS LENS
M-3	BROUZE LITE W-2100 HX5-FS HOBEL H2-A-4-4-3S 100K5B-FS MOLDCAST PCL-1-01-10-AB2P-1PU	WALL	1	130	LU100 9500	277	RECESS MOUNTED H-S 3. WALL PACK. FUSED. COULDED BY ARCHITECT/ENGINEER.

97-E-103