

NOTE: DRAWINGS SUBMITTED ARE AN ALTERNATE DESIGN REQUESTED BY W.R.KELSO CO. NOT AS DESIGNED BY FANNING & HOWIE. REF. QUOTE #970793 ALTERNATE DESIGN # 2 TAPER AND FILL ONLY.

NOTES:

- 1) INSULATION SHOWN ON THIS DRAWING IS FOAMULAR BY UCI INDUSTRIES. INSULATION IS EXTRUDED POLYSTYRENE.
- 2) LAY TAPERED BOARDS BY TYPE, AS INDICATED. THE NUMBERS FOLLOWING EACH LETTER REFER TO THICKNESS OF FILL BOARDS, AS PER CROSS-SECTION VIEW.
- 3) ALL HIPPS, VALLEYS AND CRICKETS ARE TO BE FIELD CUT. MATERIAL WILL BE SUPPLIED.
- 4) ROOF DIMENSIONS USED TO DRAW THIS PLAN WERE FROM ARCHITECT'S PLANS SUBMITTED. THE ROOFING CONTRACTOR SHOULD CHECK DIMENSIONS BEFORE MATERIAL HAS BEEN MANUFACTURED AND IN CONTACT WITH DIMENSIONS OF ANY EXISTING ROOF. ANY VARIATION AFTER PRODUCTION OF MATERIAL MAY RESULT IN ADJUSTMENT OF ORIGINAL PRICE.
- 5) APPROVED SIGNED SHOP DRAWINGS MUST BE RETURNED TO UC INDUSTRIES PRIOR TO RELEASE OF MATERIAL FOR FABRICATION.
- 6) MANUFACTURER IS NOT RESPONSIBLE FOR MISKEEPPING NOR MATERIAL SHORTAGES AFTER SIGNING FOR RECEIPT OF UCI MATERIAL.
- 7) IT IS REQUIRED THAT THE ROOFING MEMBRANE AND INSULATION BE BACKTESTED IMMEDIATELY AFTER A CEMENT TEST FOR MORE DETAILS PLEASE REFER TO CURRENT FOAMULAR LITERATURE OR CONTACT YOUR LOCAL UCI SALES REPRESENTATIVE.

## SECTION TAPERED PANELS:

|     |      |   |      |
|-----|------|---|------|
| S1. | 0.50 | - | 0.88 |
| T1. | 0.88 | - | 1.25 |
| U1. | 1.25 | - | 1.62 |
| V1. | 1.62 | - | 2.00 |
| E   | 0.50 | - | 1.00 |
| F   | 1.00 | - | 1.50 |
| G   | 0.50 | - | 1.50 |

## SECTION FILL PANELS:

0.50  
1.00  
1.50  
2.00

CRICKET TAPERED PANELS:

|   |      |   |      |
|---|------|---|------|
| G | 0.50 | – | 1.50 |
| Y | 0.00 | – | 2.00 |

CRICKET FILL PANELS:

1.00  
2.00

# FOAMULAR<sup>®</sup> Extruded Polystyrene Insulation



**OWENS CORNING**  
SPECIALTY and FOAM PRODUCTS



**FMC INDUSTRIES, INC.**

170 South Ave. P.O. Box 455  
Tallmadge, Ohio 44278  
1-800-875-1594 FAX: (216) 633-7316  
TAPER CONTROL CENTER

Project: CHESTERTON H.S.  
SWIMMING POOL  
CHESTERTON, INDIANA

Architect: FANNING &amp; HOWE

Material: THERMAPINK 25

Roofer: KELSO ROOFING

Scale: 1/16" = 1'00"      Drawn: T.L.I.  
Slope: VARIES              Checked: R.E.G.  
Date: 11/3/97              T-21897B

Drawing number: 2 OF 6

## REVISIONS

1. REVISED DRAWING FOR RELOCATION  
OF ROOF DRAINS PER W. R. KELSO.

97-SUP-63