



- A. ALL LIGHTING SWITCHES INDICATED SHALL BE REMOVED FOR REPLACEMENT WITH NEW DEVICES.
- B. INTERCOM SYSTEM - ALL SPEAKERS AND CALL SWITCHES SHALL BE DISCONNECTED AND REMOVED.
- C. CLOCK SYSTEM - ALL CLOCKS SHALL BE DISCONNECTED AND REMOVED.
- D. SEE MECHANICAL RELOCATION PLANS ON SHEETS NO. 102 AND 103 FOR MECHANICAL EQUIPMENT THAT REQUIRES ELECTRICAL DISCONNECTIONS. VERIFY WITH ELECTRICAL POWER PLANS FOR CIRCUITS TO REMAIN FOR RECONNECTION.

[illegible]

ARCHITECTS
ENGINEERS
PLANNERS

5223 Main Street
Suite 400
Evansville, In 47706

RENOVATION PROJECT FOR:
DUNELAND SCHOOL CORP.
CHESTERTON HIGH SCHOOL/MIDDLE SCHOOL
CHESTERTON, INDIANA

DRAWING TITLE: DEMOLITION PLAN - UNIT H

Project No.	998000
-------------	--------

Project Date: 11/11/2000

Drawn By: Bill

Approved By: TLM

Drawing No: _____

100	100
-----	-----