
## EXISTING - EXISTING TYPICAL STORAGE LOUNGE /TYPICAL 2001 2000 EXISTING EXISTING ROOF ROOF EXISTING MECHANICAL 2003

## **EXISTING REFLECTED CEILING PLAN** REFERENCED NOTES

- EXISTING TEXTURED SOFFIT/ WALL TO REMAIN.
- EXISTING DOOR FRAME TO REMAIN PROTECT DURING CONSTRUCTION.
- EXISTING WINDOW FRAME TO REMAIN PROTECT DURING CONSTRUCTION.
- EXISTING LARGE PENDANT METAL BRACKETS TO REMAIN -REFER TO ELECTRICAL DRAWINGS.
- EXISTING GYPSUM CEILING TO REMAIN. EXISTING LIGHT FIXTURES TO REMAIN.
- DASH LINE INDICATES EXISTING GYPSUM CEILING TO BE REMOVED IN ITS ENTIRETY.
- EXISTING LIGHT FIXTURES TO BE REMOVED.
- EXISTING MECHANICAL EQUIPMENT TO BE REMOVED IN ITS ENTIRETY - REFER TO MECHANICAL DRAWINGS FOR MORE INFORMATION.
- 10. EXISTING MECHANICAL CHASE TO REMAIN PROTECT DURING CONSTRUCTION.
- EXISTING EXPOSED CEILING AND ASSOCIATED LIGHT FIXTURES TO REMAIN.
- EXISTING LARGE PENDANT METAL BRACKETS AND LIGHT FIXTURE TO REMAIN.
- 13. EXISTING CLERESTORY WINDOW FRAME TO REMAIN PROTECT DURING CONSTRUCTION.
- 14. EXISTING TWO STORY WINDOW FRAME TO REMAIN PROTECT DURING CONSTRUCTION.
- EXISTING BEAM TO REMAIN.

## **EXISTING REFLECTED CEILING PLAN GENERAL NOTES**



REFER TO SHEETS A7.20 AND MECHANICAL, ELECTRICAL AND

- FIRE PROTECTION DRAWINGS FOR SCOPE OF NEW WORK. REFER TO ELECTRICAL PLANS FOR ADDITIONAL CEILING
- MOUNTED DEVICES AND EQUIPMENT TO BE REMOVED. CONTRACTOR TO VERIFY ALL EXISTING CEILING HEIGHTS PRIOR TO BEGINNING WORK ON ANY CEILING SCHEDULED TO RECEIVE WORK.
- FIELD VERIFY ALL EXISTING CONDITIONS. IN THE EVENT THAT AN ITEM NOT SHOWN ON THE DRAWINGS CONFLICTS WITH WORK UNDER THIS CONTRACT, CONTACT THE ARCHITECT PRIOR TO REMOVAL OF THAT ITEM. ITEMS SHOWN ARE INDICATED TO GIVE A GENERAL SCOPE OF WORK. ANY ITEMS REQUIRING REMOVAL/DEMOLITION TO PROPERLY PERFORM CONTRACT WORK BUT NOT SPECIFICALLY SHOWN, SHALL BE REMOVED BY THE CONTRACTOR AT NO ADDITIONAL COST, PROVIDING THE CONDITION WAS VISIBLE DURING BIDDING.
- 6. SHORE OR BRACE ALL EXISTING CONSTRUCTION AS REQUIRED TO PERFORM DEMOLITION WORK.
- EACH CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CORING, CUTTING, PATCHING, INFILLING, REPAIRING, REFINISHING, AND REMOVAL/REPLACEMENT OF BUILDING CONSTRUCTION REQUIRED TO ACCOMMODATE THE INSTALLATION OR REMOVAL OF THEIR WORK. ALL PATCHING, REPAIRING, AND REFINISHING SHALL BE PERFORMED BY THOSE REGULARLY INVOLVED IN THAT TRADE AND SHALL MATCH THE ADJACENT CONSTRUCTION.
- 8. PROTECT ALL EXISTING FINISHES, EQUIPMENT, AND ADJACENT WORK NOT SCHEDULED TO BE REMOVED FROM DAMAGE DURING CONSTRUCTION. ANY DAMAGED FINISHES, EQUIPMENT OR ADJACENT SURFACES SHALL BE REPAIRED OR REPLACED BY CONTRACTOR AT NO ADDITIONAL COST TO OWNER.
- THE OWNER HAS FIRST RIGHT OF REFUSAL FOR ANY MATERIAL OR EQUIPMENT REMOVED.

## **LEGEND**

PENDANT LIGHT FIXTURE TO BE REMOVED - REFER TO ELECTRICAL DRAWINGS 1' X 4' SURFACE MOUNTED LIGHT FIXTURE TO BE REMOVED - REFER TO ELECTRICAL DRAWINGS

RECESSED LIGHT FIXTURE TO REMAIN - REFER TO ELECTRICAL DRAWINGS


PENDANT LIGHT FIXTURE TO REMAIN - REFER TO ELECTRICAL DRAWINGS

MECHANICAL SUPPLY DIFFUSER TO BE REMOVED REFER TO MECHANICAL DRAWINGS

MECHANICAL RETURN/EXHAUST DIFFUSER TO BE REMOVED - REFER TO MECHANICAL DRAWINGS

EXISTING CONSTRUCTION TO BE REMOVED

EXISTING CONSTRUCTION TO REMAIN



KEY PLAN NOT TO SCALE



OAS, LLC O'HIGGINS AND ARNOLD SUJ 769 HEARTAND DR., UNIT A SUGAR GROVE, ILL **Greenbergfarto** 21 SOUTH EVERGREEN, SUITE 200 ARLINGTON HEIGHTS, IL 60005

CORPORATION

CHOOL

DUNELAND

46304

SCHOOL TERTON,

DDLE CHES

YEXISTING PARTIAL SECOND FLOOR REFLECTED CEILING PLAN

