FINISH LEGEND

CARPET - REFER TO SPECIFICATIONS FOR PATTERN AND COLOR

FINISH PLAN REFERENCED NOTES

×

NEW CARPET UNDER EXISTING STAIRS.

- PATCH AND PREPARE FLOOR FOR FLOOR FINISH AND THRESHOLD AT LOCATION WHERE MASONRY WAS REMOVED.
- 3. PAINT NEW EXPOSED CMU AND PROVIDE WALL BASE ON EXISTING NURSE CLINIC SIDE TO MATCH EXISTING ADJACENT.

NOTE:

CONTRACTOR TO VERIFY CONDITIONS AT EACH TRANSITION AND SIZE REDUCERS ACCORDINGLY.

FINISH PLAN GENERAL NOTES



. REFER TO SHEET A9.50 FOR ROOM FINISH SCHEDULES AND ADDITIONAL NOTES/500 . REFER TO SPECIFICATIONS FOR ADDITIONAL PRODUCT INFORMATION.

3. MAKE EXISTING FLOOR SLAB SMOOTH AND FLAT TO FLOOR FINISH MANUFACTURER'S TOLERANCE WITH MATERIAL SUITABLE TO FLOOR FINISH. MANUFACTURER PRIOR TO

INSTALLATION.

4. ALL TRANSITIONS BETWEEN DISSIMILAR FLOORING MATERIALS ARE TO RECEIVE A NEW

TRANSITION STRIP - REFER TO DETAILS 2/A9.10.

5. PROVIDE WALL BASE AT ALL LOCATIONS OF NEW FLOORING AND/OR NEW WALL CONSTRUCTION - UNLESS NOTED OTHERWISE.

. CARPETED AREAS ARE TO RECEIVE RUBBER STRAIGHT BASE.

1. AT AREAS WHERE PATCHING OF WALL BASE IS REQUIRED - FINISH TO MATCH ADJACENT IN MATERIAL, COLOR, HEIGHT, FINISH AND PROFILE.

PAINT PRE-FINISHED ITEMS - MATCH EXISTING COLOR, UNLESS NOTED OTHERWISE.


DO NOT PAINT PRE-FINISHED ITEMS, FACE BRICK, AND TILE FINISHES.
 AT ALL DOORS AND FRAMES INSTALLED IN EXISTING OPENINGS - PATCH AND PAINT EXISTING WALL, JAMB AND HEAD SURFACES AFTER FRAME INSTALLATION - DO NOT

10. AT ALL AREAS WHERE MECHANICAL EQUIPMENT HAS BEEN REMOVED - PATCH AND PAINT EXISTING EXPOSED CONSTRUCTION - MATCH ADJACENT EXISTING CONSTRUCTION IN MATERIAL, TEXTURE, SIZE, FINISH AND COLOR.


-RUBBER T-MOULDING

FLOOR FINISH AT LIFT TO BE PROVIDED BY LIFT MANUFACTURER.

12. TRANSITION STRIP BETWEEN LIFT AND FLOORING PROVIDED BY LIFT MANUFACTURER.



KEY PLAN







STRUCTURAL ENGINEER:
(P) 841,188,9200

OAS, LLC
O'HIGGINS AND ARNOLD SUSTAINABILITY,
769 HEATLAND DR. UNIT A SUGAR GROVE, ILLINOIS 60554

Greenbergfartow
21 South Purgreen, Suite 200
ARLINGTON HEIGHTS, IL 60005

ELAND SCHOOL CORPORATION

NIN OFFICE RENOVATIONS AT:

RTON MIDDLE SCHOOL (CMS)

AVENUE, CHESTERTON, INDIANA

CHESTE MORGAN

2018

CER MG
PSN
A
A
D: 03/18/100R FINISH PLAN

PROJECT NUMBER: 18-603 REVIPED FOUND THE PSN AND THE PARTIAL FIRST FLOOR FIN

A9.10

AR10800173

STATE OF